

HT# 06-5-15348R

Harrett County Department of Public Health

23266

1586A Storage

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: JERRY HAMILTON

PROPERTY LOCATION: HWY 421 (TIRZAH DR)

NEW REPAIR EXPANSION

SUBDIVISION THOMAS LASATER LOT # 3

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD 57'x68'

Proposed Wastewater System Type: PUMP TO CONVENTIONAL

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years

Permit conditions: LOT CUT FOR FOUNDATION. PUMP NOW REQUIRED DUE TO NEW GRADE

No expiration

Authorized State Agent: [Signature] RS

Date: 10/10/06

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: JERRY HAMILTON

PROPERTY LOCATION: HWY 421 (TIRZAH DR)

SUBDIVISION THOMAS LASATER LOT # 3

Facility Type: SFD (57'x68') New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** PUMP TO CONVENTIONAL (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable
PUMP TO CONVENTIONAL (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons
 Pump Tank Size 1000 gallons

Exact length of each trench 100 feet
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 24 inches
 (Trench bottoms shall be level to +/-1/4" in all directions)

Pump Requirements: 10 ft. TDH vs. 23 GPM

2 TRENCHES
 Trench Spacing: 9 Feet on Center
 Soil Cover: 12 inches
 (Maximum soil cover shall not exceed 36" above the trench bottom)

Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total

**If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] RS

Date: 10/10/06

Construction Authorization Expiration Date: 10/10/11

HTE# 06-5-15348R

Permit # 23266

15869-Storage

Harnett County Department of Public Health
Site Sketch

PROPERTY LOCATION: Hwy 421 (TIRZAH DR)

ISSUED TO: ~~JERRY~~ HAMILTON

SUBDIVISION THOMAS LPSATER

LOT # 3

Authorized State Agent:

~~_____~~ RS

Date: 10/10/06

