

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: John Campbell Builder
PROPERTY LOCATION: 1116
SUBDIVISION: Colonial Hills
LOT # 52
Type of Structure: SFD- 56x48 JBR
Proposed Wastewater System Type: Pump to Gravel
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement: No
Pump Required: No
Type of Water Supply: Public
Permit conditions: SFB out Plumbing shall be at ground level or higher where shown & if 18 to 24" Ditch Depth can be maintained then pump may not be required - meet onsite maintain all set backs

Authorized State Agent: J. W. ... Date: 2.26.07 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: John Campbell Builder
PROPERTY LOCATION: 1116
SUBDIVISION: Colonial Hills
LOT # 52
Facility Type: SFD- 56x48-3BR New
Basement? No
Type of Wastewater System: Gravel (Initial)
Wastewater Flow: 360 GPD
(See note below, if applicable) 290 LF of LPP (Repair)

Installation Requirements/Conditions

Septic Tank Size: 1000 gallons
Pump Tank Size: 1000 gallons IF Needed
Exact length of each trench: 1x240 feet
Trenches shall be installed on contour at a Maximum Trench Depth of: 18-24 inches
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
(Pump Requirements: ft. TDH vs. GPM)
Aggregate Depth: 6 inches below pipe, 2 inches above pipe, 12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: J. W. ... Date: 02.26.07 SEE ATTACHED SITE SKETCH
Construction Authorization Expiration Date: 02.26.2012

