



**SYSTEM TYPE:**

CONVENTIONAL	_____	TRENCH DEPTH	<u>17"</u>	PUMP TANK	<u>NO</u>
INNOVATIVE	<u>EZ LAY</u>	FILL REQUIRED	<u>1-6" (TOP LINES)</u>	CUT-OFF DRAIN	<u>NO</u>
FLOW	<u>360</u> GPD	TRENCH REQUIRED	<u>340</u>	SHWT (BLG)	<u>29-31"</u>
LTAR	<u>.26</u> TEXTURE <u>SCL/SL</u>	TRENCH AVAILABLE	<u>340+</u>	BLDG. FOOTPRINT	<u>73' x 55'</u>
REDUCTION %	<u>25</u>	TRENCH SPACING	<u>9'</u>	REPAIR	<u>OFF-SITE (PREVIOUSLY LAID-OUT BY HCHD)</u>

+ SOIL BORING (30" - SHWT)

**Waste Water Disposal System Design**  
**Gatewest Subdivision**  
 Lemuel Black Road  
 (NCSR 1125)  
 Anderson Creek, Harnett  
 County North Carolina

**Protocol Sampling Service, Inc.**  
 Post Office Box 31133  
 Raleigh, North Carolina 27622

Lot #: 7 (JUNE 26, 2008)  
 SCALE: 1" = 20'  
 PROJ. #: 07-04

A 0-20" G S VOR NS/SP  
 20-31" SBL SCL FR S/SP  
 10' x 7' @ 32"  
 P3.22

B 0-6" G L VOR SS/SP  
 6-22" G S VOR NS/SP  
 22" SBL SCL FR S/SP  
 10' x 7' @ 31"  
 P3.25