

HTE# 07-5-1659622


Harnett County Department of Public Health

24350

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: WILLIE JUNIOR LASSITER PROPERTY LOCATION: NORRINGTON RD
 NEW ☐ REPAIR ☐ EXPANSION ☒ SUBDIVISION: MCNEILL ACRES LOT # 1
 Type of Structure: SFD (30'x80') Site Improvements required prior to Construction Authorization Issuance:
 Proposed Wastewater System Type: CONVENTIONAL
 Projected Daily Flow: 480 GPD
 Number of bedrooms: 4 Number of Occupants: 8 max
 Basement ☐ Yes ☒ No
 Pump Required: ☐ Yes ☒ No ☐ May be required based on final location and elevations of facilities
 Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well 100 feet Permit valid for: ☒ Five years
 Permit conditions: ☐ No expiration

Authorized State Agent: Date: 11/19/07

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: WILLIE JUNIOR LASSITER PROPERTY LOCATION: NORRINGTON RD
 SUBDIVISION: MCNEILL ACRES LOT # 1
 Facility Type: SFD (30'x80') ☐ New ☒ Expansion ☐ Repair
 Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No
 Type of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 480 GPD
 (See note below, if applicable ☐)
PUMP TO CONVENTIONAL (Repair)

Installation Requirements/Conditions


Septic Tank Size EXISTING gallons Exact length of each trench 60 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size _____ gallons Trenches shall be installed on contour at a Soil Cover: 12 inches
 Maximum Trench Depth of: 24 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to $\pm 1/4"$ in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
60' OF TRENCH TO BE ADDED TO END OF EXISTING DRAINFIELD 2 inches above pipe
EXACT END OF DRAINING MUST BE LOCATED 12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:  Date: 11/19/07
 Construction Authorization Expiration Date: 11/19/12

HTE# 07-5-16596RR

Permit # 24350

Harnett County Department of Public Health Site Sketch

ISSUED TO: WILLIE JUNIOR LOSSITER PROPERTY LOCATOR: NORRINGTON RD
SUBDIVISION MCNEILL ACRES LOT # 1
Authorized State Agent: [Signature] RS (OLIVER TOLKSDORF) Date: 11/19/07

