

HTE# 075-16849

Harnock County Department of Public Health 23731

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: SHC HOLDINGS INC PROPERTY LOCATION: SR1565 SILAS HAYES RD
 SUBDIVISION: Hunters Point LOT # 36
 NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:
 Type of Structure: SFD
 Proposed Wastewater System Type: 25% RCP System
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: James E. Mantantz Date: 3-1-07 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: SHC HOLDINGS INC PROPERTY LOCATION: SR1565 SILAS HAYES RD
 SUBDIVISION: Hunters Point LOT # 36
 Facility Type: SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% RCP System MANITZ (initial) Wastewater Flow: 360 GPD
 (See note below, if applicable LPP Repair
25% RCP Duction System (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 5 x 60 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size 1600 gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 24-18-16 inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to +1-1/4" 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
 Conditions: 1st Ditch 24", 2nd 22", 3rd 20", 4th 18", 5th 16" MAX 12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Mantantz Date: 3-1-07
 Construction Authorization Expiration Date: 3-1-12

HTE# 07-5-16849

Permit # 23731

Harnett County Department of Public Health Site Sketch

ISSUED TO: SHC HOLDINGS INC PROPERTY LOCATOR: 50565 Silas Hayes RD
SUBDIVISION Hunters Point LOT # 36

Authorized State Agent: James E. Manhart Date: 3-2-07

