

HTE# 07-50016875
R

Harford County Department of Public Health

23670

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Steve Jernigan PROPERTY LOCATION: 1108
 NEW REPAIR 40x48 EXPANSION SUBDIVISION: Yorkshire Plantation LOT # 140
 Type of Structure: SFD- 58 x 37 JBR Site Improvements required prior to Construction Authorization Issuance: plw septic easement
 Proposed Wastewater System Type: Pump to 25% Reduction sys.
 Projected Daily Flow: 360 GPD Revised 11-13-09 by JHW/REH
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 50 feet Permit valid for: Five years
 Permit conditions: Met on site - Pump to septic Easement Area No expiration
Maintain all set backs 18" max d. to depth.

Authorized State Agent: Ju WAREHS Date: 2-22-07 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Steve Jernigan PROPERTY LOCATION: 1108
 SUBDIVISION Yorkshire Plantation LOT # 140
 Facility Type: SFD- 58 x 37 50 x 48 New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Pump to 25% Red sys. (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable 360 LF of LPP (Repair))

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench ~~30~~ 1x225 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 4 inches
 Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/- 1/4" in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
 Aggregate Depth: _____ inches above pipe
 Conditions: _____ inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: Ju WAREHS SEE ATTACHED SITE SKETCH
 Date: 2-22-07 11-13-09
 Construction Authorization Expiration Date: 2-22-2012 11-13-2014

HTE# 07-50016875R

Permit # 23670

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: 1108

ISSUED TO: Steve Jenigan

SUBDIVISION Yalshire Plantation LOT # 140

Authorized State Agent:

J. W. REHS

Date: 2.22.07 11-13-09

Meet onsite
for final
layout
Maintain All
setbacks
Install 1x225 &
25% Reduction system at 18"



Lot 141
Easement

