

ADDRESS : ~~104 WEATHERBY CT~~ SUBDIV: HUNTERS POINT 45 LOTS  
 CONTRACTOR : STANCIL BUILDERS INC. PHONE : (919) 639-2073  
 OWNER : SHC HOLDINGS INC#26 PHONE :  
 PARCEL : 07-0691- - -0023- -25-  
 APPL NUMBER: 07-50016956 CP NEW RESIDENTIAL (SFD)

DIRECTIONS : ~~HUNTERS POINT #26~~  
 HWY 27 TO COATS LEFT ON 55 TOWARDS  
 ANGIER, RIGHT ON SILAS HAYES RD SUBD ON  
 RIGHT.  
 T/S: 02/26/2007 11:46 AM DJOHNSON --

STRUCTURE: 000 000 40X60 3BDR CRAWL W/ GARAGE  
 FLOOD ZONE . . . . : FLOOD ZONE X  
 # BEDROOMS . . . . . : 3.00 PROPOSED USE . . . . . : SFD  
 SEPTIC - EXISTING? . . . . : NEW WATER SUPPLY . . . . . : COUNTY

PERMIT: CPSF 00 CP \* SFD

TYP/SQ	REQUESTED COMPLETED	INSP RESULT	DESCRIPTION RESULTS/COMMENTS
B101 01	11/13/14	DT	R*BLDG FOOTING / TEMP SVC POLE VRU #: 002598031
	11/13/14	AP	T/S: 11/13/2014 01:14 PM DETAYLOR -----
A814 01	12/09/14	SB	ADDRESS CONFIRMATION TIME: 17:00 VRU #: 002606812
	12/09/14	AP	T/S: 12/09/2014 09:10 AM SBENNETT ----- 104 WEATHERBY CT ANGIER 27501 POST # ON HOME T/S: 12/09/2014 09:10 AM SBENNETT -----
B103 01	12/09/14	DT	R*BLDG FOUND & TEMP SVC POLE TIME: 17:00 VRU #: 002606804
	12/09/14	AP	T/S: 12/09/2014 12:14 PM DETAYLOR -----
B105 01	1/06/15	DT	R*OPEN FLOOR VRU #: 002614031
	1/06/15	AP	T/S: 01/06/2015 02:00 PM DETAYLOR -----
R425 01	1/30/15	DT	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002623015
	1/30/15	DA	T/S: 01/29/2015 02:24 PM DJOHNSON ----- T/S: 01/30/2015 09:42 AM DETAYLOR ----- Need engineer repair for broken T3 truss above left bedroom Okay to side and insulate
I129 01	2/10/15	TI	R*INSULATION INSPECTION VRU #: 002625840
	<u>2/10/15</u>	<u>APDT</u>	
R425 02	2/10/15	TI	FOUR TRADE ROUGH IN TIME: 17:00 VRU #: 002626174
	<u>2/10/15</u>	<u>APDT</u>	T/S: 02/09/2015 02:58 PM DJOHNSON -----

COMMENTS AND NOTES

**DAVID MILLER, PE**  
6300 Creedmoor Rd, STE 170#363  
Raleigh, NC 27612  
(919) 422-8932 (Office) ; DAVE@DMA-PA.COM

February 4, 2015

Stancil Builders, Inc.  
466 Stancil Road  
Angier, NC 27501  
E-mailed to flstancil@embarqmail.com (Attn. : Mr. Freddie L. Stancil)

Re.: Engineering Analysis – Framing  
Lot 26 Hunters Point, Johnston County, NC  
Job No.: 15DDM-0204D

To whom it may concern/ Inspections Dept.:

The undersigned has observed the cracked web of the T-3 roof truss (member 8-11) for the above referenced site. Based on the cracked section and the internal forces the crack should be sistered on each side at least 2 feet in either direction of the crack (4ft) with four 10d nails on each side of the crack (both sides) to adequately transfer the loading conditions.

Sincerely,

David Miller, PE

DEM/15DDM-0204D



# 0750016956