

HTE# 07-5-1693R

# Harrison County Department of Public Health

23488

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Raynor Builders, Inc.

PROPERTY LOCATION: SR 1429 Chalybeate Road

SUBDIVISION Dexterfield

LOT # 37

NEW  REPAIR  EXPANSION

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD 50'x60'

Proposed Wastewater System Type: pump to conventional

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well \_\_\_\_\_ feet

Permit valid for:  Five years

Permit conditions: \_\_\_\_\_

No expiration

Authorized State Agent: Bryan McSwain, P.E.

Date: 4/11/2007

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Raynor Builders, Inc.

PROPERTY LOCATION: SR 1429

SUBDIVISION Dexterfield

LOT # 37

Facility Type: SFD 50'x60'  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* pump to conventional (Initial)

Wastewater Flow: 360 GPD

(See note below, if applicable )

pump to conventional (Repair)

### Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Pump Tank Size 1000 gallons

Exact length of each trench 2x150 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 18-24 inches

(Trench bottoms shall be level to +1/4" in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 6-12 inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

Conditions: Drain Lines to be installed in easement for lot 37

12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McSwain, P.E.

Date: 4/11/2007

Construction Authorization Expiration Date: 4/12/2007

HTE# 07-5-16993R

Permit # 23488

# Harnett County Department of Public Health Site Sketch

ISSUED TO: Raynor Builders, Inc. PROPERTY LOCATOR: SR 1429 Chalybeate  
SUBDIVISION: Dexterfield LOT # 37

Authorized State Agent: Bryan McLean, P.S. Date: 4/11/2017

EASEMENT FOR  
Lot 37  
52'

