

HTE# 07-5-17001

Harnett County Department of Public Health

23770

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Randy STEPHENSON

PROPERTY LOCATION: SR1565 Silas Hayes RD

NEW REPAIR EXPANSION

SUBDIVISION Huntens Point LOT # 13

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD

Proposed Wastewater System Type: 25% REDUCTION System

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet

Permit valid for: Five years

Permit conditions: DO NOT CUT OR DISTURB TERRACE IN WHICH SYSTEM WELL BE INSTALLED.

No expiration

Authorized State Agent: James E. Markant

Date: 3-30-07

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Randy STEPHENSON

PROPERTY LOCATION: SR1565 Silas Hayes RD

SUBDIVISION Huntens Point LOT # 13

Facility Type: SFD New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% REDUCTION (Initial)

Wastewater Flow: 360 GPD

(See note below, if applicable)

25% LPP Repe (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Exact length of each trench 2 X 150 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size 1000 gallons

Trenches shall be installed on contour

Soil Cover: 6 inches

Maximum Trench Depth of: 28-318 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to $\pm 1/4$ " in all directions)

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

Conditions: DONOT CUT OR DISTURB TERRACE IN WHICH SYSTEM WILL BE INSTALLED

12 inches total

STAPDOWNS WELL BE NEEDED

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markant

Date: 3-30-07

Construction Authorization Expiration Date: 3-30-12

HTE# 07-5-17001

Permit # 23770

Harnett County Department of Public Health Site Sketch

ISSUED TO: RANDY STEPHENSON PROPERTY LOCATOR: SR 1565 SELAS HAYES RD
SUBDIVISION Hunters Point LOT # 13

Authorized State Agent: James E. Markant Date: 3-30-07

* Septic Contractor to
MEET ON SITE
Prior to INSTALL!
for system layout
and detail.

