

HTE# 07-5-1764

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: STANCI BUILDERS
PROPERTY LOCATION: SR1403 Cokesbury RD
SUBDIVISION: Cokesbury Park LOT # 52
NEW [X] REPAIR [] EXPANSION []
Type of Structure: SFD
Proposed Wastewater System Type: 25% REDUCTION MANHOLE
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [] Yes [X] No
Pump Required: [X] Yes [] No
Type of Water Supply: [] Community [X] Public [] Well
Permit valid for: [X] Five years [] No expiration

Authorized State Agent: James E. Marshant Date: 6-20-07 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: STANCI BUILDERS
PROPERTY LOCATION: SR1403 Cokesbury RD
SUBDIVISION: Cokesbury Park LOT # 52
Facility Type: SFD [X] New [] Expansion [] Repair []
Basement? [] Yes [X] No Basement Fixtures? [] Yes [X] No
Type of Wastewater System** 25% REDUCTION (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable []) 25% REDUCTION SYSTEM MANHOLE (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 4 x 60 feet Trench Spacing: 9 Feet on Center
Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
Maximum Trench Depth of: 30-18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
Pump Requirements: ft. TDH vs. GPM Aggregate Depth: 6 inches below pipe 2 inches above pipe 12 inches total
Conditions: 4-1/2" sch 40 VALVES ON MANHOLES

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Marshant Date: 6-20-07
Construction Authorization Expiration Date: 6-20-12

HTE# 07-5-17564

Permit # 23966

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: SR1403 CoKeshburg RD

ISSUED TO: STANCI BUILDERS INC SUBDIVISION CoKeshburg Park LOT # 52

Authorized State Agent: Jane E. Mohant Date: 6-20-07

