


HTE# 07-5-17701
07-5-17703

Harrison County Department of Public Health 24062

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: DONNA & ROBERT WALDSCHMIDT
PROPERTY LOCATION: SUBDIVISION ROSS McRAE BRAE LOT # 11
NEW [X] REPAIR [] EXPANSION []
Type of Structure: SFD (81'x63')
Proposed Wastewater System Type: CONVENTIONAL
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [] Yes [X] No
Pump Required: [] Yes [X] No [] May be required based on final location and elevations of facilities
Type of Water Supply: [] Community [X] Public [] Well Distance from well 100 feet
Permit valid for: [X] Five years [] No expiration
Permit conditions:

Authorized State Agent:  RS Date: 6/12/07 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: DONNA & ROBERT WALDSCHMIDT
PROPERTY LOCATION: SUBDIVISION ROSS McRAE BRAE LOT # 11
Facility Type: SFD (81'x63') [X] New [] Expansion [] Repair
Basement? [] Yes [X] No Basement Fixtures? [] Yes [X] No
Type of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable []) CONVENTIONAL (Repair)

Installation Requirements/Conditions

4 TRENCHES

Septic Tank Size 1000 gallons
Pump Tank Size _____ gallons
Exact length of each trench 75 feet
Trenches shall be installed on contour at a
Maximum Trench Depth of: 18 inches (Trench bottoms shall be level to +/- 1/4" in all directions)
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
Pump Requirements: _____ ft. TDH vs. _____ GPM
Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total
Conditions: VERIFY FIELD LAYOUT AFTER SITE HAS BEEN CLEARED & PRIOR TO INSTALLATION

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:  RS Date: 6/12/07
Construction Authorization Expiration Date: 6/12/12

HTE# 07-5-17701

Permit # 24062

07-5-17703

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR:
ISSUED TO: DONNA & ROBERT WALOSCHMIDT SUBDIVISION ROSS McRAE BRAE LOT # 11
Authorized State Agent: [Signature] RS (OLIVER TOLKSDORF) Date: 6/12/07

