

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Regency Homes
PROPERTY LOCATION: 1210
SUBDIVISION: Persimmon Hill
LOT # 10

Type of Structure: SFD-56x40-3BR
Proposed Wastewater System Type: 2' wide Chamber
Projected Daily Flow: 300 GPD
Number of bedrooms: 3 Number of Occupants: 6 max

Basement: No
Pump Required: May be required based on final location and elevations of facilities
Type of Water Supply: Well Distance from well: 100 feet

Permit conditions: Meet code for final layout maintain all setbacks
STUB out plumbing shallow at ground level or higher where shown
Must Be in 8ft. 12" approved cover

Authorized State Agent: [Signature] Date: 9-12-08

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

SEE ATTACHED SITE SKETCH

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Regency Homes
PROPERTY LOCATION: 1210
SUBDIVISION: Persimmon Hill
LOT #

Facility Type: SFD-56x40-3BR New
Basement? No
Type of Wastewater System: 2' wide Chamber
(Initial) Wastewater Flow: 300 GPD

Installation Requirements/Conditions

Septic Tank Size: 1000 gallons
Pump Tank Size:
Number of trenches: 1
Exact length of each trench: 480 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Maximum Trench Depth of: 12 inches
Pump Requirements: ft. TDH vs. GPM
Aggregate Depth: inches below pipe, inches above pipe, inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 9-12-08
Construction Authorization Expiration Date: 9-12-2013

HTE# 07-500-17802RR

Permit # 25059

Harnett County Department of Public Health Site Sketch

ISSUED TO: Regency Homes

PROPERTY LOCATOR: 1210

SUBDIVISION Redemon #11

LOT # 10

Authorized State Agent: J. W. [Signature]

Date: 9-12-08

