

HTE# 07-50017803RR

Harnett County Department of Public Health

25061

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Regency Homes
PROPERTY LOCATION: 1210
SUBDIVISION: Persimmon Hill LOT # 11
NEW [X] REPAIR [] EXPANSION []
Type of Structure: SFD-57x41 3BR
Proposed Wastewater System Type: 25% Reduction system
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [] Yes [X] No
Pump Required: [] Yes [] No [X] May be required based on final location and elevations of facilities
Type of Water Supply: [] Community [X] Public [] Well Distance from well 100 feet
Permit conditions: Stub out plumbing shallow, at ground level or higher meet on site for final layout maintain all setbacks

Authorized State Agent: [Signature] Date: 09-12-08 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Regency Homes
PROPERTY LOCATION: 1210
SUBDIVISION: Persimmon Hill LOT # 11
Facility Type: SFD-57x41-3BR [X] New [] Expansion [] Repair
Basement? [] Yes [X] No Basement Fixtures? [] Yes [X] No
Type of Wastewater System** 25% Reduction system (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable [X]) 25% Reducto-system (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size _____ gallons
Number of trenches 1
Exact length of each trench 300 feet
Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a
Maximum Trench Depth of: 18 inches
Soil Cover: 6 inches
(Trench bottoms shall be level to +/-1/4"
(Maximum soil cover shall not exceed
in all directions) 36" above the trench bottom)
Pump Requirements: _____ ft. TDH vs. _____ GPM
Aggregate Depth: _____ inches below pipe
Conditions: _____ inches above pipe
_____ inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 9-12-08
Construction Authorization Expiration Date: 7-12-2013

HTE# 07-500-17803RR

Permit # 25061

Harnett County Department of Public Health Site Sketch

ISSUED TO: Agency Homes

PROPERTY LOCATOR: 1210

SUBDIVISION: Persimmon Hill

LOT # 11

Authorized State Agent: [Signature]

Date: 09-12-08

SR 1210
100

15' Street scape Buffer

Some 25%
Reduction
System
Remain

73'

33'

DRIVE

Garage

Meet onsite
for Final Layout
maintain All
setBACKS

STUBOUT Plumbing
shallow AT ground
level or higher
Drain field is
to start near
Front Property Line

12' wide

Some
25% Reduction
SYSTEM
Remain

89'

Red 75'

Blue 75'

Red 75'

Blue 75'

10

15

15'

110'

100'

Old Field Loop