

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Kenneth Cummings PROPERTY LOCATION: NC 27
 SUBDIVISION: TWIGEN Point LOT # 23
 NEW REPAIR EXPANSION
 Type of Structure: SFO-56x63-3BR Site Improvements required prior to Construction Authorization Issuance:
This permit Replaces permit # 24292
 Proposed Wastewater System Type: Pump to 25% Reduction
 Projected Daily Flow: 360 GPD SYSTEM
 Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 50 feet Permit valid for: Five years
 Permit conditions: Met on site for final layout maintain all setbacks No expiration
STUB OUT plumbing shallow, At ground level or higher where shown, AND IF
18" pitch depth can be maintained Then pump may not be required
 Keep man line 15' from top of trench

Authorized State Agent: Joe WARR Date: 10-12-07 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Kenneth Cummings PROPERTY LOCATION: NC 27
 SUBDIVISION: TWIGEN Point LOT # 23
 Facility Type: SFO-56x63 3BR New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Pump to 25% Red. sys (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable 25% Red. System (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 2 x 90 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to $\pm 1/4"$ 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
 Aggregate Depth: _____ inches above pipe
 Conditions: _____ inches total

**If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: Joe WARR Date: 10-12-07 SEE ATTACHED SITE SKETCH
 Construction Authorization Expiration Date: 10-12-2012

HTE# 07-50018263R

Permit # 24369

Harnett County Department of Public Health Site Sketch

ISSUED TO: Kenneth Cummings PROPERTY LOCATOR: NC 27
 SUBDIVISION: Tilken Point LOT # 23
 Authorized State Agent: Ju W. Aei Date: 10-12-07

