

HTE# 07-50018591R

Harris County Department of Public Health

23553

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: JBC Developers
PROPERTY LOCATION: 1115
SUBDIVISION: CREVIEW LOT # 208
Type of Structure: SFO-56x36 ZBR
Proposed Wastewater System Type: Pump to 25% Reduction system
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement: No
Pump Required: No
Type of Water Supply: Public
Permit conditions: Meet on site for final layout maintain all x+BARK, keep drain lines with area shown for septic system keep drain line 10' from Septic Casement Line

Authorized State Agent: J. W. ... Date: 11-6-07 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: JBC Developers
PROPERTY LOCATION: 1115
SUBDIVISION: CREVIEW LOT # 208
Facility Type: SFO-56x36 ZBR New
Basement? No
Type of Wastewater System: Pump to 25% Red. system (Initial)
Wastewater Flow: 360 GPD
(See note below, if applicable) 360 LFM LPP (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons
Pump Tank Size 1000 gallons
Exact length of each trench 1x225 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Maximum Trench Depth of: 18 max inches
(Pump Requirements: ft. TDH vs. GPM)
Aggregate Depth: inches below pipe, inches above pipe, inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: J. W. ... Date: 11-6-07 SEE ATTACHED SITE SKETCH
Construction Authorization Expiration Date: 11-6-2012

HTE# 07-500-18591R

Permit # 23553

# Harnett County Department of Public Health Site Sketch

ISSUED TO: JBC Developers

PROPERTY LOCATOR: 1115

SUBDIVISION Crestview

LOT # 208

Authorized State Agent: Ju LAR

Date: 11-6-07

Meet onsite for Final Layout. Maintain all setbacks.  
Keep septic line within area marked. Install 1x25 of 25% Reduction System  
at 18" keep drain lines 10' from septic easement line

