

HTE# 07-50018609

Har... County Department of Public Health

24371

### Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Wynn Const.

PROPERTY LOCATION: NC27

SUBDIVISION Tingen Pointe

LOT # 22

Site Improvements required prior to Construction Authorization Issuance:

NEW  REPAIR  EXPANSION

Type of Structure: SFD-40x38-3BR

Proposed Wastewater System Type: 25% Reduction system

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well 50 feet

Permit valid for:  Five years

Permit conditions: Meet on site for final layout maintain all set backs  No expiration

STUB out plumbing shallow, AT Ground level or higher where shown

Authorized State Agent: Ju Wars

Date: 10-16-07

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

### Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: WYNN CONST.

PROPERTY LOCATION: NC27

SUBDIVISION Tingen Pointe

LOT # 22

Facility Type: SFD-40x38 3BR  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* 25% Red. system (Initial)

Wastewater Flow: 360 GPD

(See note below, if applicable  Pump to 25% Red. system (Repair)

#### Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Exact length of each trench 1x180 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size \_\_\_\_\_ gallons

Trenches shall be installed on contour at a

Soil Cover: 6 inches

Maximum Trench Depth of: 18-24 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/-1/4"

36" above the trench bottom)

in all directions)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

Aggregate Depth: \_\_\_\_\_ inches below pipe

Aggregate Depth: \_\_\_\_\_ inches above pipe

Conditions: \_\_\_\_\_ inches total

\*\*If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: Ju Wars

Date: 10-16-07

SEE ATTACHED SITE SKETCH

Construction Authorization Expiration Date: 10-16-2012

HTE# 07-500-18609

Permit # 24371

# Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: NC 27


ISSUED TO: Wynn Cons.

SUBDIVISION Tingen Pointe

LOT # 22

Authorized State Agent: Ju W. Lee

Date: 10-16-07



STUB out Plumbing shallow  
 At ground level or higher  
 Where shown. maintain  
 All setBacks  
 Meet on site

Install 1x180 of 25%  
 Reduction system At 18 to 24"

JWORN Loop