

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: BRAD CUMMINGS
PROPERTY LOCATION: TRIPP RD
SUBDIVISION: VINEYARD GREEN LOT # 5
Type of Structure: SFD (68'x50')
Proposed Wastewater System Type: 25% REDUCTION SYSTEM
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement: No
Pump Required: May be required based on final location and elevations of facilities
Type of Water Supply: Public
Distance from well: 100 feet
Permit valid for: Five years

Authorized State Agent: [Signature] Date: 8/7/08 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: BRAD CUMMINGS
PROPERTY LOCATION: TRIPP RD
SUBDIVISION: VINEYARD GREEN LOT # 5
Facility Type: SFD (68'x50') New
Basement: No
Type of Wastewater System: 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD
Pump To CONVENTIONAL (Repair)

Installation Requirements/Conditions
Septic Tank Size: 1000 gallons
Pump Tank Size: [blank] gallons
Number of trenches: 1
Exact length of each trench: 225 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Maximum Trench Depth of: 15-18 inches
Pump Requirements: [blank] ft. TDH vs. [blank] GPM
Aggregate Depth: [blank] inches below pipe, [blank] inches above pipe, [blank] inches total
Conditions: MINIMUM OF 6" OF COVER NEEDED OVER DRAINFIELD. ALL CONDITIONS OF ATTACHED PROPOSAL FROM HALOWEN & ASSOCIATES MUST BE FOLLOWED

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: [Signature] Date: [blank]

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 8/7/08
Construction Authorization Expiration Date: 8/7/13

# Lot 5, Vineyard - Green

## On-Site Wastewater Design Specifications

House Footprint: See drawing  
 No Foundation Drain  
 Bedrooms: 3 (Daily Flow 360 gallons)

**LEGEND**

- \* EIP
- Supply Line
- ⊕ Proposed Well
- ⊗ Existing Well
- Septic Tank
- Pump Tank
- D-Box
- ⊞ Pressure Manifold




07-50018691

**Initial System:** Gravity, serial distribute to 225 ft accepted status drainlines  
 Installed off contour parallel to rear property line at 16" to 18" inches below grade  
 Soil LTAR 0.4 gal/day/sqft

**Repair System:** Pump to 2 X 150ft conventional drainlines  
 Installed off contour parallel to rear property line at 18" to 30" inches below grade  
 Soil LTAR 0.4 gal/day/sqft

Lines flagged at site on 9-ft centers.

Initial/Repair	Line #	Color	Drainline Length(ft)	Relative Elevation of ground left side	Relative Elevation of ground right side	- Elevation of Trench Bottom
Repair	1	R	150	100.35	99.43	97.93
Repair	2	Y	150	99.76	98.88	97.18
Initial	3	B	80	98.65	98.43	97.15
Initial	4	R	75	98.23	98.12	96.73
Initial	5	Y	70	97.91	97.91	96.41
<b>Septic Tank:</b>				98.19		
<b>Pump Tank:</b>				97.83		
<b>Total:</b>			<b>525</b>	<b>EIP=100 (feet)</b>		




\* HOUSE IS CURRENTLY PINNED ON SITE. \*




Lot 5, Vineyard Green


Line 1		Trench	
Length (ft)	Ground	Trench	Depth (in)
0	100.35	97.93	29
45	99.77	97.93	22
90	99.33	97.93	17
135	99.00	97.93	13
150	99.43	97.93	18




Line 2		Trench	
Length (ft)	Ground	Trench	Depth (in)
0	99.76	97.18	31
45	99.45	97.18	27
90	98.95	97.18	21
135	98.61	97.18	17
150	98.68	97.18	18




Line 3		Trench	
Length (ft)	Ground	Trench	Depth (in)
0	98.65	97.15	18
45	98.54	97.15	17
83	98.43	97.15	15



Line 4		Trench	
Length (ft)	Ground	Trench	Depth (in)
0	98.23	96.73	18
40	98.175	96.73	17
78	98.12	96.73	17




Line 5		Trench	
Length (ft)	Ground	Trench	Depth (in)
0	97.91	96.41	18
35	97.91	96.41	18
71	97.91	96.41	18



Lot 5, Vineyard Green

Septic Tank Profile

Ground Elevation 98.19  
 Tank Inlet 97.94 (3" below natural grade)  
 Tank Outlet (Inlet -2") 97.77 \*\*



Supply Line Length 60 ft  
 Supply Line Inlet 97.77  
 Supply Line Outlet (1% fall) 97.15

To achieve gravity distribution (no pump tank) the plumbing must stub from the house at -98 ft or higher, or about 3" below natural grade at the right rear corner of the house. You will need to add about 6 inches of fill at the rear of the house to adequately cover the septic tank and supply line. Fill should not be added within 25ft of the rear property line over the repair drainfield.

If the plumbing does not stub out high enough, then a pump tank will be necessary to distribute effluent to the drainfield.