

HTE# 07-5-18733

Harnett County Department of Public Health

24402

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: CWL CONTRACTORS
NEW [X] REPAIR [ ] EXPANSION [ ]
Type of Structure: SFD
Proposed Wastewater System Type: 25% REDUCTION SYSTEM
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [ ] Yes [X] No
Pump Required: [ ] Yes [ ] No [X] May be required based on final location and elevations of facilities
Type of Water Supply: [ ] Community [X] Public [ ] Well
Permit conditions: [X] Five years [ ] No expiration

Authorized State Agent: James E. Manhart Date: 10-31-07 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: CWL CONTRACTORS
PROPERTY LOCATION: 581403 HARNETT CTR RD
SUBDIVISION: QUAIL GLEN LOT # 6
Facility Type: SFD [X] New [ ] Expansion [ ] Repair [ ]
Basement? [ ] Yes [X] No Basement Fixtures? [ ] Yes [X] No
Type of Wastewater System: 25% REDUCTION (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable) 25% REDUCTION (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 4x 80 feet Trench Spacing: 9 Feet on Center
Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
Maximum Trench Depth of: 28-718 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
Pump Requirements: ft. TDH vs. GPM Aggregate Depth: 6 inches below pipe 2 inches above pipe 12 inches total
Conditions:

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: James E. Manhart Date: 10-31-07 SEE ATTACHED SITE SKETCH
Construction Authorization Expiration Date: 10-31-12

HTE# 07-5-18733

Permit # 24402

# Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: 501403 HARNETT Central

ISSUED TO: CWW CONTRACTORS

SUBDIVISION QUAIL GLEN

LOT # 6

Authorized State Agent: James E. Marshall

Date: 10-31-07

