

HT# 07-5-18187

Har... County Department of Public Health

24225

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: CMN Bottlers INC
PROPERTY LOCATION: SR 2005 Brickmill
SUBDIVISION: Collestone LOT # 24
NEW [X] REPAIR [ ] EXPANSION [ ]
Type of Structure: SFD
Proposed Wastewater System Type: 25% REDUCTION System
Projected Daily Flow: 480 GPD
Number of Bedrooms: 4 Number of Occupants: 8 max
Basement [ ] Yes [X] No
Pump Required: [X] Yes [ ] No [ ] May be required based on final location and elevations of facilities
Type of Water Supply: [ ] Community [X] Public [ ] Well Distance from well \_\_\_\_\_ feet Permit valid for: [X] Five years [ ] No expiration
Permit conditions: ALLOWANCE of Pool & Pool HOUSE to be DETERMINED AFTER SYSTEM INSTALL.

Authorized State Agent: James E. Markham Date: 8-21-07 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: CMN BUILDERS INC
PROPERTY LOCATION: SR 2005 Brickmill RD
SUBDIVISION: Collestone LOT # 24
Facility Type: SFD [X] New [ ] Expansion [ ] Repair [ ]
Basement? [ ] Yes [X] No Basement Fixtures? [ ] Yes [X] No
Type of Wastewater System\*\* 25% REDUCTION System (Initial) Wastewater Flow: 480 GPD
(See note below, if applicable [ ])
25% REDUCTION System (Repair)

Installation Requirements/Conditions
Septic Tank Size 1200 gallons Exact length of each trench 100 feet Trench Spacing: 9 Feet on Center
Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
MANHOLE 4x1/2 sch 40 valves Maximum Trench Depth of: 24-30-20 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
(Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM)
Aggregate Depth: 6 inches below pipe, 2 inches above pipe, 12 inches total
Conditions: Pool & Pool HOUSE NOT ALLOWED AT THIS POINT

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: James E. Markham Date: 8-21-07 SEE ATTACHED SITE SKETCH
Construction Authorization Expiration Date: 8-21-12

HTE# 07-5-18187

Permit # 24225

# Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: SR 2005 BRICKMILL RD

ISSUED TO: CMN Builders Inc

SUBDIVISION Cottleston

LOT # 24

Authorized State Agent: James E. Manhart

Date: 8-21-07

