

HTE# 08-500-19555

Harnett County Department of Public Health

24681

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: H & H Const. PROPERTY LOCATION: 1125
SUBDIVISION: FOREST OAKS LOT # 201

NEW REPAIR EXPANSION
Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFO- 46x52 - 4 BR

Proposed Wastewater System Type: 25% Reduction system

Projected Daily Flow: 430 GPD

Number of bedrooms: 4 Number of Occupants: 8 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 50 feet Permit valid for: Five years

Permit conditions: STUB out Plumbing shallow at ground level or higher where No expiration

Shown. Meet on site maintain All set Backs - Install French drain

As shown - French Drain to be min of 34" Deep with gravel to within 6" of surface

Authorized State Agent: J. Waters Date: 04-02-08 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: H & H Const. PROPERTY LOCATION: 1125
SUBDIVISION: FOREST OAKS LOT # 201

Facility Type: SFO- 46x52 - 4 BR New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% Reduction sys. (Initial) Wastewater Flow: 480 GPD

(See note below, if applicable) 25% Reduction System (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 2x130 feet Trench Spacing: 9 Feet on Center

Pump Tank Size _____ gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)

(Trench bottoms shall be level to +/-1/4" in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
Aggregate Depth: _____ inches above pipe

Conditions: _____ inches total

**If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: J. Waters Date: 04-02-08 SEE ATTACHED SITE SKETCH

Construction Authorization Expiration Date: 04-02-2013

HTE# 08-500-19555

Permit # 24681

Harnett County Department of Public Health Site Sketch

ISSUED TO: H&H Cont.

PROPERTY LOCATOR: 1125

SUBDIVISION: FOREST OAK

LOT # 201

Authorized State Agent:

J. WARS

Date: 04-02-08

INSTALL 2x130
4 25% Reduction
SYSTEM AT
18"

Meet onsite for Final Layout
INSTALL French DRAIN ABOVE SEPTIC
SYSTEM AS SHOWN - 52" DEEP WITH
GRAVEL TO WITHIN 6" OF
SURFACE

