SOUTHEASTEN SOIL & ENVIRONMENTAL ASSOC, INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION Forest Oaks **LOT** 201

INITIAL SYSTEM Approved 25% reduction **REPAIR** Approved 25% reduction

DISTRIBUTION 0-box **DISTRIBUTION** 0-box

BENCHMARK 100.0 **LOCATION** Nail in tree

NO. BEDROOMS 4

proposed LTAR = 0.5 gpd/ft² could go higher -

LINE	FLAG COLOR	ELEVATION	ACTUAL LENGTH
Initial 1	R	100.0	125'
Initial 2	W	98.58	125'
3	R	97.0	125'
4	W	95.50	125'

BY M EAKER **DATE** 03/2008

Add French Drain to 54" (Gravel up to 6" from surface)

Typ Profile = 0-44 cs (VFr, wg-) some washed sand pockets
44-48+ SCL (Fr, SBK) unmottled