

HTE# 08-519595

Harnett County Department of Public Health

24706

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: HUGH SURLS BUILDERS LLC

PROPERTY LOCATION: LASATER RD (SR 2046)

NEW REPAIR EXPANSION

SUBDIVISION JC ADAMS INC

LOT # 4

Type of Structure: SFD (66'x58')

Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: ACCEPTED SYSTEM

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years
 No expiration

Permit conditions:

Authorized State Agent:  Date: 3/28/08

Date: 3/28/08

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: HUGH SURLS BUILDERS INC

PROPERTY LOCATION: LASATER RD

SUBDIVISION JC ADAMS INC

LOT # 4

Facility Type: SFD (66'x58') New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** ACCEPTED SYSTEM (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable)

FILL SYSTEM (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Number of trenches 1

Pump Tank Size _____ gallons

Exact length of each trench 385 feet

Trench Spacing: 9 Feet on Center

Trenches shall be installed on contour at a

Soil Cover: 6-8 inches

Maximum Trench Depth of: 12-14 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/-1/4"

36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: _____ inches below pipe

Conditions: MINIMUM OF 6" OF COVER NEEDED OVER DRAINFIELD

Aggregate Depth: _____ inches above pipe

OPERATIONS PERMIT WILL BE ISSUED AFTER FINAL GRADING OVER DRAINFIELD

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:  Date: 3/28/08

Date: 3/28/08

Construction Authorization Expiration Date: 3/28/13

HTE# 08-5-19595

Permit # 24706

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: LASATER RD (SR2046)

ISSUED TO: HUGH SURLES BUILDERS LLC SUBDIVISION JC ADAMS INC LOT # 4

Authorized State Agent: [Signature] ES (OLIVER TOLKSON) Date: 3/28/08

