

HTE# 08-500-19640R

Harnett County Department of Public Health

24686

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Matthew Leach PROPERTY LOCATION: Dove Rd
 SUBDIVISION: Johnsenville Township LOT # Tract 2
 NEW REPAIR EXPANSION
 Type of Structure: SFD - 48x50 - 4BR Site Improvements required prior to Construction Authorization Issuance: 35.36 ac
 Proposed Wastewater System Type: Pump to Gravel
 Projected Daily Flow: 480 GPD
 Number of bedrooms: 4 Number of Occupants: 8 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 50 feet Permit valid for: Five years
 Permit conditions: Meet onsite for Final layout maintain all No expiration
Set Backs Tank must be 15' from basement & 15' from Future Pool
location

Authorized State Agent: Ju Warr Date: 04-08-08 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Matthew Leach PROPERTY LOCATION: Dove Rd
 SUBDIVISION: Johnsenville Township LOT # Tract 2
 Facility Type: SFD-48x50-4BR New Expansion Repair 35.36 ac
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Pump to Gravel (Initial) Wastewater Flow: 480 GPD
 (See note below, if applicable Pump to 25% Reduction (Repair)
 SYSTEM

Installation Requirements/Conditions

Septic Tank Size 1200 gallons Exact length of each trench 3x140 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size 1200 gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/-1/4" in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
 Conditions: _____ 12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: Ju Warr Date: 04-08-08 SEE ATTACHED SITE SKETCH
 Construction Authorization Expiration Date: 04-08-2013

HTE# 08-500-19640R

Permit # 24686

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: Dove Rd

ISSUED TO: Matthew Leach

SUBDIVISION Johnsonville Township

LOT # Tract 2
35.364c

Authorized State Agent:

J. W. [Signature]


Date: 04-08-08

Meet onsite for Final layout
Maintain All set Backs
Septic & Pump Tank must be
15' from home & Future
Pool location

Suitable soils
Are 110' from upper
Property line & straight
Back 400' - There is
to be No TRAFFIC or
Building within that
Area.

No Driving or parking on top
of any portion of septic system

Install 3x 140' of gravel
at 18"



Dove Rd

To NE 24/27 →