

HTE# 08-5-19940

Harnett County Department of Public Health 24640

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Comfort Homes INC
NEW [X] REPAIR [ ] EXPANSION [ ]
Type of Structure: SFD
Proposed Wastewater System Type: 25% REDUCTION System
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [ ] Yes [X] No
Pump Required: [X] Yes [ ] No [X] May be required based on final location and elevations of facilities
Type of Water Supply: [ ] Community [X] Public [ ] Well
Permit conditions:

PROPERTY LOCATION: SR1448 ATKINS RD
SUBDIVISION: STETSON LOT # 21
Site Improvements required prior to Construction Authorization Issuance:
Permit valid for: [X] Five years [ ] No expiration

Authorized State Agent: James E. Markham Date: 5-14-08 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Comfort Homes INC PROPERTY LOCATION: SR1448 ATKINS RD
SUBDIVISION: STETSON LOT # 21
Facility Type: SFD [X] New [ ] Expansion [ ] Repair
Basement? [ ] Yes [ ] No Basement Fixtures? [ ] Yes [ ] No
Type of Wastewater System: 25% REDUCTION System (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable [ ] ) PUMP TO MANIFOLD 25% REDUCTION System (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 4x 80 feet Trench Spacing: 9 Feet on Center
Pump Tank Size 1000 gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
MANIFOLD Specs 40 1/2 inch 40 inches Maximum Trench Depth of: 24" max (Maximum soil cover shall not exceed 36" above the trench bottom)
(Trench bottoms shall be level to +/- 1/4" in all directions)
Pump Requirements: 2' supply - 2' pressure ft. TDH vs. \_\_\_\_\_ GPM Aggregate Depth: 6 inches below pipe 12 inches above pipe 12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: James E. Markham Date: 5-14-08 SEE ATTACHED SITE SKETCH
Construction Authorization Expiration Date: 5-14-13

HTE# 08-5-19940

Permit # 24640

# Harnett County Department of Public Health Site Sketch

ISSUED TO: Comfort Homes INC PROPERTY LOCATOR: SR1448 ATKENS RD  
SUBDIVISION: STETSON LOT # 21

Authorized State Agent: James E. Marshall Date: 5-14-08

