

HTE# 08-5-20159

# Harris County Department of Public Health

24918

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: SCOTT LEE HOMES, INC

PROPERTY LOCATION: TRULOVE RD (SR452)  
SUBDIVISION JONATHAN RIDGE LOT # 28

NEW  REPAIR  EXPANSION

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD (55' x 45')

Proposed Wastewater System Type: PUMP TO 25% REDUCTION

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well 100 feet

Permit valid for:  Five years  
 No expiration

Authorized State Agent: [Signature] RS Date: 6/19/08 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: SCOTT LEE HOMES, INC

PROPERTY LOCATION: TRULOVE RD  
SUBDIVISION JONATHAN RIDGE LOT # 28

Facility Type: SFD (55' x 45')  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* PUMP TO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable ) LPP (Repair)

<b>Installation Requirements/Conditions</b>	Number of trenches <u>1</u>	
Septic Tank Size <u>1000</u> gallons	Exact length of each trench <u>300</u> feet	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size <u>1000</u> gallons	Trenches shall be installed on contour at a	Soil Cover: <u>6</u> inches
	Maximum Trench Depth of: <u>12-17</u> inches	(Maximum soil cover shall not exceed
	(Trench bottoms shall be level to +/- 1/4"	36" above the trench bottom)
	in all directions)	

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM \_\_\_\_\_ inches below pipe

Conditions: MINIMUM OF 6" OF COVER NEEDED OVER DRAIN FIELD Aggregate Depth: \_\_\_\_\_ inches above pipe  
\_\_\_\_\_ inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] RS Date: 6/19/08

Construction Authorization Expiration Date: 6/19/13

HTE# 08-5-20159

Permit # 24918

# Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: TRULOVE RD SR1452

ISSUED TO: SCOTT LEE HOMES INC SUBDIVISION JONATHAN RIDGE LOT # 28

Authorized State Agent: ~~\_\_\_\_\_~~ RS (OLIVER TOLKSOORE) Date: 6/19/08

