

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Cumberland Homes
PROPERTY LOCATION: 1111
SUBDIVISION: Ashcroft
LOT # 123
Type of Structure: SFD-28x45-3BR
Proposed Wastewater System Type: 25% Reduction system
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement: No
Pump Required: No
Type of Water Supply: Public
Permit conditions: Meet on site for final layout maintain all setbacks

Authorized State Agent: J. WARR Date: 09-10-08 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met.

ISSUED TO: Cumberland Homes
PROPERTY LOCATION: 1111
SUBDIVISION: Ashcroft
LOT # 123
Facility Type: SFD-28x45-3BR New
Basement? No
Type of Wastewater System: 25% Reduction system
(Initial) Wastewater Flow: 360 GPD
(See note below, if applicable) 25% Reduction sys. (Repair)

Installation Requirements/Conditions
Septic Tank Size: 1000 gallons
Pump Tank Size:
Number of trenches: 1
Exact length of each trench: 180 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Maximum Trench Depth: 18-24 inches
Pump Requirements:
Aggregate Depth:
Conditions:

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: J. WARR Date: 09-10-08
Construction Authorization Expiration Date: 9-10-2013

HTE# 08500-20764

Permit # 25051

## Harnett County Department of Public Health Site Sketch

ISSUED TO: Cumberland Homes

PROPERTY LOCATION: 1111  
SUBDIVISION: Ashcroft

LOT # 123

Authorized State Agent: Joe WRS

Date: 09-10-08

85'

Repair  
Area

92'

10

10

10

180

5

10

26'

26'

40'

10' REFUSE

85'

Road

Meet onsite for Final  
Layout  
MAINTAIN ALL SETBACKS  
INSTALL 180' of 25% Reduc.  
system at 18 to 24" Deep  
STUB out plumbing  
shallow, at ground  
level or higher  
where shown.