

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Wynn Construction

PROPERTY LOCATION: Hwy 27
SUBDIVISION: Tingen Pointe LOT # 41

NEW [x] REPAIR [] EXPANSION []

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD 65135

Proposed Wastewater System Type: 25% Reduction System

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement [] Yes [x] No

Pump Required: [] Yes [] No [x] May be required based on final location and elevations of facilities

Type of Water Supply: [] Community [x] Public [] Well Distance from well _____ feet

Permit valid for: [x] Five years [] No expiration

Permit conditions:

Authorized State Agent: Bryan McSwain LEHS Date: 5/27/2010 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Wynn Construction

PROPERTY LOCATION: Hwy 27
SUBDIVISION: Tingen Pointe LOT # 41

Facility Type: SFD [x] New [] Expansion [] Repair

Basement? [] Yes [] No Basement Fixtures? [] Yes [] No

Type of Wastewater System** 25% Reduction System (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable []) Pump to 25% Reduction System (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size _____ gallons
Number of trenches 4
Exact length of each trench 50 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6-12 inches
Maximum Trench Depth of: 18 inches
(Trench bottoms shall be level to +/- 1/4" in all directions)
(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
Aggregate Depth: _____ inches above pipe _____ inches total

Conditions: Run drain lines on contour. No utilities allowed in the system for repair areas. All water lines must be at least 10ft. from any part of septic system. PERMIT Based on Consultants proposal

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McSwain LEHS Date: 5/27/2010
Construction Authorization Expiration Date: 5/27/2010

HTE# 08-5-21024R

Permit # 25982

Harnett County Department of Public Health Site Sketch

ISSUED TO: Wynn Construction PROPERTY LOCATOR: Hwy 27
SUBDIVISION Tingen Pointe LOT # 41

Authorized State Agent: Bryan McSwain REHS Date: 5/27/2010

