

HTE# 08500-2147

Harnett County Department of Public Health

25205

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: D. Walsh Const. PROPERTY LOCATION: 1139
SUBDIVISION: Tingen Place LOT # 52

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD 38x37-3BR

Proposed Wastewater System Type: 25% Reduction system - Pump

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: _____ max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years

Permit conditions: Meet onsite for final layout - STUB out Plumbing shallow No expiration

At ground level or higher where shown and 18 to 24" Pitch Depth can be

Maintained then Pump MAY NOT be Required

Authorized State Agent: J. Williams

Date: 11-24-08

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: D. Walsh Const.

PROPERTY LOCATION: 1139

SUBDIVISION: Tingen Place

LOT # 52

Facility Type: SFD-38x37-3BR New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pump to 25% Reduction system (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable) Pump to 25% Reduction Sys (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Pump Tank Size 1000 gallons

If Needed

Number of trenches 1

Exact length of each trench 100 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 18-24 inches

(Trench bottoms shall be level to +/- 1/4"

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 6 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

_____ inches below pipe

Aggregate Depth: _____ inches above pipe

Conditions: _____ inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: J. Williams

Date: 11-24-08

Construction Authorization Expiration Date: 11-24-2013

HTE# 08-500-21247

Permit # 25205

Harnett County Department of Public Health Site Sketch

ISSUED TO: D. Walsh Court


PROPERTY LOCATOR: 1131

SUBDIVISION Tinsgen Place

LOT # 52

Authorized State Agent: Ju Laks

Date: 11-24-08



Meet onsite for Final layout
 Maintain all set backs
 Stub out Plumbing
 Shallow - at ground level
 or higher where shown
 And if 18 to 24" Ditch
 Depths can be maintained
 Pump may not be required
 Install 150' of 25% Reduction
 System at 18-24" Deep.