

HTE# 09-500-21652

Harnett County Department of Public Health

25363

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: AQ Contracting PROPERTY LOCATION: JR 1139
NEW REPAIR EXPANSION SUBDIVISION: Tingen Place LOT # 37

Type of Structure: SFD- 53x26-3BR

Proposed Wastewater System Type: Pump to 25% Reduction Sys.

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit conditions: Meet on site for final layout - maintain all setbacks

Sub out plumbing shall be at ground level or higher where shown and if 18" or 24" depth can be maintained then pump may not be needed

Authorized State Agent: Ju W. A. Date: 07-07-09

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Permit valid for: Five years No expiration

SEE ATTACHED SITE SKETCH

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: AQ Contracting PROPERTY LOCATION: JR 1139
SUBDIVISION: Tingen Place LOT # 37

Facility Type: SFD- 53x26-3BR New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pump to 25% Reduction system (Initial) Wastewater Flow: _____ GPD

(See note below, if applicable) Pump to 25% Reduction Sys. (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size 1000 gallons
Number of trenches 1
Exact length of each trench 180 feet
Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a
Soil Cover: 6 inches
Maximum Trench Depth of: 18-24 inches
(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: _____ inches below pipe
_____ inches above pipe
_____ inches total

Conditions: _____

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: Ju W. A. Date: 07-09-09

Construction Authorization Expiration Date: 07-09-2014

HTE# 09-520-21652

Permit # 25363

Harnett County Department of Public Health Site Sketch

ISSUED TO: AJ Contracting

PROPERTY LOCATOR: SR 1139

SUBDIVISION Tinsler Place

LOT # 37

Authorized State Agent: Qu LAN

Date: 07-25-09

Meet onsite for Final Layout
MAINTAIN ALL SETBACKS

STUB OUT PLUMBING SHALLOW, AT GROUND LEVEL
OR HIGHER WHERE SHOWN AND IF 18" TO 24"
DITCH DEPTHS CAN BE MAINTAINED

PUMP MAY NOT
BE REQUIRED

