

HTE# 09-5-22157

Harnett County Department of Public Health

25441

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Eric Graf PROPERTY LOCATION: 511412 Christen Light RD
 NEW REPAIR EXPANSION SUBDIVISION: LAKEVIEW LOT # 3
 Type of Structure: SFD Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: 25% REDUCTION (MANITEE)
 Projected Daily Flow: 600 GPD
 Number of bedrooms: 5 Number of Occupants: 10 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: CONTRACTOR TO MEET ON SITE PRIOR TO INSTALL. No expiration

Authorized State Agent: James E. Marshall Date: 10-21-09 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: ERIC GRAF PROPERTY LOCATION: 511412 Christen Light
 SUBDIVISION: LAKEVIEW LOT # 3
 Facility Type: SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** MANITEE TO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 600 GPD
 (See note below, if applicable)
25% REDUCTION / LPP (Repair)
 Installation Requirements/Conditions
 Septic Tank Size 1200 gallons Number of trenches 3
 Pump Tank Size 1000 gallons Exact length of each trench 125 feet Trench Spacing: 9 Feet on Center
MANITEE Spec's 3-1/4" valves Trenches shall be installed on contour at a Soil Cover: 6 inches
2" supply Maximum Trench Depth of: 22-20-10 inches (Maximum soil cover shall not exceed
 in all directions) (Trench bottoms shall be level to +/- 1/4" 36" above the trench bottom)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
 Conditions: CONTRACTOR TO MEET ON SITE PRIOR TO INSTALL. 12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Marshall Date: 10-21-09
 Construction Authorization Expiration Date: 10-21-14

HTE# 09-5-22157

Permit # 25441

Harnett County Department of Public Health Site Sketch

ISSUED TO: ERIC GRAF PROPERTY LOCATOR: 521412 Christian Loop RD
SUBDIVISION LAKE VIEW LOT # 3

Authorized State Agent: James E. Markant REAS Date: 10-20-09

* MAY NEED FRENCH DRAIN WITH INSTALL. OF SEPTIC SYSTEM.

* CONTRACTOR TO MEET ON SITE PRIOR TO INSTALL.

