

HTE# 09-5-22353

Harnett County Department of Public Health

25291

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Jason Price Construction
PROPERTY LOCATION: SR 1201 Raderwood Rd.
SUBDIVISION: Carolina Seasons LOT # 71
NEW [X] REPAIR [] EXPANSION []
Type of Structure: SFD 56' x 40'
Proposed Wastewater System Type: 25% Reduction System
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [] Yes [X] No
Pump Required: [] Yes [X] No
Type of Water Supply: [] Community [X] Public [] Well
Permit conditions: Permit valid for: [X] Five years [] No expiration

Authorized State Agent: [Signature] Date: 7/10/2009 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Jason Price Construction
PROPERTY LOCATION: SR 1201
SUBDIVISION: Carolina Seasons LOT # 71
Facility Type: SFD [X] New [] Expansion [] Repair []
Basement? [] Yes [X] No Basement Fixtures? [] Yes [] No
Type of Wastewater System** 25% Reduction (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable []) 25% Reduction (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size [] gallons
Number of trenches 3
Exact length of each trench 60 feet
Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a Maximum Trench Depth of: 36-22 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
Soil Cover: 24 inches
Aggregate Depth: [] inches below pipe [] inches above pipe [] inches total

Pump Requirements: [] ft. TDH vs. [] GPM
Conditions: Start Drain line to start at 36 inches & run to 22 inches. I + HOUSE IS NOT BUILT ACCORDING TO SITE PLAN
DO NOT INSTALL SEPTIC SYSTEM

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: [] Date: []

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 7/10/2009
Construction Authorization Expiration Date: 7/10/2014

HTE# 09-5-22353

Permit # 25291

Harnett County Department of Public Health Site Sketch

ISSUED TO: Jason Price Construction PROPERTY LOCATOR: SR 1201 Ponderosa Rd.
SUBDIVISION Carolina Seasons LOT # 71

Authorized State Agent: [Signature] Date: 7/10/2009

