HTE# 09-5-22661

## Harnett County Department of Public nealth

25652

Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: MARKS RD ISSUED TO: WM. KENT PIERCE INC. SUBDIVISION ASHEFORD EXPANSION Site Improvements required prior to Construction Authorization Issuance: Type of Structure: SFD (45 ×52) Proposed Wastewater System Type: CONJENTIONAL Projected Daily Flow: 360 Number of bedrooms: \_\_\_\_3 Number of Occupants: 6 Basement Yes No Pump Required: ☐Yes ► No ☐ May be required based on final location and elevations of facilities Type of Water Supply: 
Community Public Well Distance from well to 6 feet Permit valid for: Five years Permit conditions: ■ No expiration The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Persuit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Wm. Kent PIERCE INC PROPERTY LOCATION: MARKS RO SUBDIVISION ASHEFORD Expansion Repair Basement? 

Yes No Basement Fixtures? 

Yes CONVENTIONAL (Initial) Wastewater Flow: 360 Type of Wastewater System\*\* (See note below, if applicable CONVENTIONAL Installation Requirements/Conditions Number of trenches Septic Tank Size \_\_\_\_\_ gallons Exact length of each trench 50 Trench Spacing: Trenches shall be installed on contour at a Pump Tank Size gallons Soil Cover: 12-18 Maximum Trench Depth of: 24-30 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_\_ft. TDH vs. \_\_\_\_\_ GPM inches below pipe Conditions: WATER LINE MUST BE AT LEAST 10 FROM ALL PARTS OF THE PUTTING SERTIC SYSTEM AND REPAIR AREA. ALL OTHER UTILITIES MAY NOT ENCROACH ON ANY PART OF THE SEPTIC SYSTEM AND REPAIR FORA \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative\_Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is sometime compliance with the provisions of the laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent: \_ Construction Authorization Expiration Date: 8 3

HTE# 69-5-22-66	1
-----------------	---

Permit # <u>25652</u>

## Harnett County Department of Public Health Site Sketch

0	PROPERTY LOCATON: MARKS RD	
ISSUED TO: Wm. KENG PERCE INC	SUBDIVISION ASHEFORD	LOT # <u>2</u>
Authorized State Agent:	estouver Toursdor Date: 8/26/09	

