

HTE# 09-22721

Harnett County Department of Public Health

25632

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Stencil Builders

PROPERTY LOCATION: Micro Tower Rd.

SUBDIVISION: Pattons Point II

LOT # 183

NEW [checked] REPAIR [] EXPANSION []

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD 40x60'

Proposed Wastewater System Type: 25% Reduct. in

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement [] Yes [checked] No

Pump Required: [] Yes [checked] No [] May be required based on final location and elevations of facilities

Type of Water Supply: [] Community [checked] Public [] Well Distance from well _____ feet

Permit valid for: [checked] Five years [] No expiration

Permit conditions:

Authorized State Agent: Ben McSwain RCH

Date: 10/9/2009

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Stencil Builders

PROPERTY LOCATION: Micro Tower Rd.

SUBDIVISION: Pattons Point II

LOT # 183

Facility Type: SFD [checked] New [] Expansion [] Repair []

Basement? [] Yes [] No Basement Fixtures? [] Yes [] No

Type of Wastewater System** 25% Reduct. in System (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable [])

25% Reduct. in System (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Pump Tank Size _____ gallons

Number of trenches 1

Exact length of each trench 150 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 18-30 inches

(Trench bottoms shall be level to +/- 1/4"

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 12-18 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: _____ inches below pipe

_____ inches above pipe

_____ inches total

Conditions: No Utilities Allowed in System or Repair Areas Water line must be at least 10 ft. from any part of septic system

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature:

Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:

Ben McSwain RCH

Date: 10/9/2009

Construction Authorization Expiration Date: 10/9/2014

HTE# 09-5-22721

Permit # 25632

Harnett County Department of Public Health Site Sketch

ISSUED TO: Stencil Builders PROPERTY LOCATOR: Micro Tower Rd.
SUBDIVISION: Patten's Point II LOT # 183

Authorized State Agent: Ryan McLean, REHS Date: 10/9/2009

