

HTE# 09-5-22723

# Harnett County Department of Public Health

25650

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Stencil Builders PROPERTY LOCATION: SR 1141 Micro Tower Rd.  
 SUBDIVISION Pattar's Point LOT # 187  
 NEW  REPAIR  EXPANSION   
 Type of Structure: SFD 46' X 60'  
 Proposed Wastewater System Type: Conventional  
 Projected Daily Flow: 360 GPD  
 Number of bedrooms: 3 Number of Occupants: 6 max  
 Basement  Yes  No  
 Pump Required:  Yes  No  May be required based on final location and elevations of facilities  
 Type of Water Supply:  Community  Public  Well Distance from well \_\_\_\_\_ feet Permit valid for:  Five years  
 Permit conditions: \_\_\_\_\_  No expiration

Authorized State Agent: Bryan McWin, R.E.H.S. Date: 11/20/2009 SEE ATTACHED SITE SKETCH  
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Stencil Builders PROPERTY LOCATION: Micro Tower Rd.  
 SUBDIVISION Pattar's Point LOT # 187  
 Facility Type: SFD  New  Expansion  Repair  
 Basement?  Yes  No Basement Fixtures?  Yes  No  
 Type of Wastewater System\*\* conventional (Initial) Wastewater Flow: 360 GPD  
 (See note below, if applicable  conventional (Repair))

**Installation Requirements/Conditions**  
 Septic Tank Size 1000 gallons Number of trenches 3  
 Pump Tank Size \_\_\_\_\_ gallons Exact length of each trench 50 feet Trench Spacing: 9 Feet on Center  
 Trenches shall be installed on contour at a Soil Cover: 6-12 inches  
 Maximum Trench Depth of: 18-24 inches (Maximum soil cover shall not exceed  
 (Trench bottoms shall be level to  $\pm 1/4$ " 36" above the trench bottom)  
 in all directions)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM \_\_\_\_\_ 6 inches below pipe  
 Aggregate Depth: \_\_\_\_\_ 2 inches above pipe  
 \_\_\_\_\_ 12 inches total

Conditions: Ditches to be NO DEEPER than 24 inches. No utilities  
Allowed in septic system + or repair area. Water line must be 10ft  
from any part of septic system

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McWin, R.E.H.S. Date: 11/20/2009  
 Construction Authorization Expiration Date: 11/20/2014

HTE# 09-5-22723

Permit # 25650

# Harnett County Department of Public Health Site Sketch

ISSUED TO: Stancil Builders PROPERTY LOCATION: Micro Tower Rd.  
SUBDIVISION Patterson Point LOT # 157

Authorized State Agent: Bryan McSwain, R.E.A.S. Date: 11/20/2019

