

HTE# 09-5-22756

Hammet County Department of Public Health

25622

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Andrew Milton PROPERTY LOCATION: 421
 SUBDIVISION: Manor Hills LOT # 1

NEW REPAIR EXPANSION
 Type of Structure: SFD 52' x 53' Site Improvements required prior to Construction Authorization Issuance:
 Proposed Wastewater System Type: 25% Reduction System
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: Bryan McSwain, P.E. Date: 9/18/2009 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Andrew Milton PROPERTY LOCATION: 421
 SUBDIVISION: Manor Hills LOT # 1

Facility Type: SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% Reduction System (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable
25% Reduction System (Repair)

Installation Requirements/Conditions

Septic Tank Size <u>1000</u> gallons	Number of trenches <u>4</u>	Exact length of each trench <u>75</u> feet	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size _____ gallons	Trenches shall be installed on contour at a	Maximum Trench Depth of: <u>20</u> inches	Soil Cover: <u>8-10</u> inches
	(Trench bottoms shall be level to +/-1/4" in all directions)	(Maximum soil cover shall not exceed 36" above the trench bottom)	

Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe

Conditions: Run drain lines on contour. Contractor to meet on site to layout system. NO Utilities allowed in septic system or Repair area. Water line must be at least 10ft. from any part of septic system. Aggregate Depth: _____ inches above pipe _____ inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McSwain, P.E. Date: 9/18/2009
 Construction Authorization Expiration Date: 9/18/2014

HTE# 09-5-22756

Permit # 25622

Harnett County Department of Public Health Site Sketch

ISSUED TO: Andrew Milton PROPERTY LOCATOR: 421
SUBDIVISION: Manor Hills LOT # 1

Authorized State Agent: Bryan McSwain, R.E.H.S. Date: 9/18/2009

*Contractor to meet on site prior to installing system for layout

