

HTE# 09-5-22773R

Harnett County Department of Public Health

25433

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: HAL MCKENNON

PROPERTY LOCATION: SL1566 Popes Lake RD

NEW [x] REPAIR [] EXPANSION []

SUBDIVISION Popes Lake PL I LOT # 3

Type of Structure: SFD

Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type:

Projected Daily Flow: 480 GPD

Number of bedrooms: 4 Number of Occupants: 8 max

Basement [] Yes [x] No

Pump Required: [] Yes [] No [x] May be required based on final location and elevations of facilities

Type of Water Supply: [] Community [x] Public [] Well Distance from well _____ feet

Permit valid for: [x] Five years [] No expiration

Permit conditions:

Authorized State Agent: James E. Markon

Date: 9-21-09

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: HAL MCKENNON

PROPERTY LOCATION: SL1566 Popes Lake RD

Facility Type: SFD [x] New [] Expansion [] Repair

SUBDIVISION Popes Lake PL I LOT # 3

Basement? [] Yes [x] No Basement Fixtures? [] Yes [x] No

Type of Wastewater System** 25% REDUCTION System (Initial) Wastewater Flow: 480 GPD

(See note below, if applicable [])

25% REDUCTION / LPP Repair (Repair)

Installation Requirements/Conditions

Septic Tank Size 1200 gallons

Number of trenches 5

Pump Tank Size _____ gallons

Exact length of each trench 80 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 20" inches

(Trench bottoms shall be level to +/- 1/4"

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 6 inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

12 inches total

Conditions:

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature:

Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:

James E. Markon

Date:

9-21-09 (1/20/10)

Construction Authorization Expiration Date:

9-21-14

HTE# 09-5-22773R

Permit # 25433

Harnett County Department of Public Health Site Sketch

ISSUED TO: HAI MCKINNON

PROPERTY LOCATOR: SR 1566 Popes Lake RD

SUBDIVISION Popes Lake P1

LOT # 3

Authorized State Agent: James E. Mankant Wasas

Date: 1-20-10

*AREA ON property
where DRAINAGES
ARE to Be Located
WILL NEED ADDITIONAL
SOIL Added where
Trees were removed.

*RUN Electric
LINE DOWN
PROPERTY LINE
then cut ACROSS
TO HOME.

