

HTE# 09-5-23127

Harnett County Department of Public Health

25764

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: KENNETH CUMMINGS PROPERTY LOCATION: MARKS RD
 SUBDIVISION: ASHFORD LOT # 68
 NEW REPAIR EXPANSION
 Type of Structure: SFD (59'x39') Site Improvements required prior to Construction Authorization Issuance:
 Proposed Wastewater System Type: PUMP TO 25% REDUCTION SYSTEM
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: [Signature] REAS Date: 11/2/09 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: KENNETH CUMMINGS PROPERTY LOCATION: MARKS RD
 SUBDIVISION: ASHFORD LOT # 68
 Facility Type: SFD (59'x39') New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** PUMP TO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable) PUMP TO 25% REDUCTION SYSTEM (Repair)

Installation Requirements/Conditions
 Septic Tank Size 1000 gallons
 Pump Tank Size 1000 gallons
 Number of trenches 1
 Exact length of each trench 180 feet
 Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 18-12 inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to +/- 1/4" ^{SEE DRAWING} 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
 Aggregate Depth: _____ inches above pipe
 Conditions: MINIMUM 6" OF COVER NEEDED OVER DRAINFIELD. WATER LINE
MUST BE 10' FROM SEPTIC SYSTEM

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] REAS Date: 11/2/09
 Construction Authorization Expiration Date: 11/2/14

HTE# 09-5-23127

Permit # 25764

Harnett County Department of Public Health Site Sketch

ISSUED TO: KENNETH CUMMINGS PROPERTY LOCATOR: MARKS RD
SUBDIVISION ASHFORD LOT # 68

Authorized State Agent: ~~RENS (OLIVER TOLKOFF)~~ Date: 11/2/09

* SYSTEM IS FLAGGED. IF
FLAGS ARE MISSING CALL
HCHD TO REFLAG SYSTEM
PRIOR TO INSTALLATION

