

HTE# 09-5-23172

Harnett County Department of Public Health

25703

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Jonathan Lee Turlington PROPERTY LOCATION: SR 2003 Melamb Rd
 NEW REPAIR EXPANSION SUBDIVISION: Johnny Turlington LOT # 1
 Type of Structure: SFD Site Improvements required prior to Construction Authorization Issuance:
 Proposed Wastewater System Type: 25% REDUCTION
 Projected Daily Flow: 480 GPD
 Number of bedrooms: 4 Number of Occupants: 8 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100' feet Permit valid for: Five years
 Permit conditions: No expiration

Authorized State Agent: James E. Markant Date: 11-17-09 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Jonathan Lee Turlington PROPERTY LOCATION: SR 2003 Melamb Rd
 Facility Type: SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% REDUCTION System (Initial) Wastewater Flow: 480 GPD
 (See note below, if applicable)
25% REDUCTION System (Repair)
 Installation Requirements/Conditions
 Septic Tank Size 1200 gallons Number of trenches 2
 Pump Tank Size _____ gallons Exact length of each trench 160 feet Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a Maximum Trench Depth of: 28-18 inches Soil Cover: 6 inches
 (Trench bottoms shall be level to +/- 1/4" in all directions) (Maximum soil cover shall not exceed 36" above the trench bottom)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
 _____ inches above pipe
 _____ inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markant Date: 11-17-09
 Construction Authorization Expiration Date: 11-17-14

HTE# 09-5-23172

Permit # 25703

Harnett County Department of Public Health Site Sketch

ISSUED TO: Jonathon Lee Turkelington PROPERTY LOCATOR: SR 2003 McLamb RD
SUBDIVISION Johnny Turkelington LOT # 1

Authorized State Agent: James E. Markant Date: 11-17-09

