

HTE# 09-5-23222

## Harnett County Department of Public Health

25704

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Robert + Mary FauceHe Jr PROPERTY LOCATION: SR 1403 Cokesburg RD  
 NEW ☒ REPAIR ☐ EXPANSION ☐ SUBDIVISION: COVENESS LOT # A  
 Type of Structure: SFD Site Improvements required prior to Construction Authorization Issuance:  
 Proposed Wastewater System Type: 25% REDUCTION  
 Projected Daily Flow: 360 GPD  
 Number of bedrooms: 3 Number of Occupants: 6 max  
 Basement ☐ Yes ☒ No  
 Pump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilities  
 Type of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well \_\_\_\_\_ feet Permit valid for: ☒ Five years  
 Permit conditions: \_\_\_\_\_ ☐ No expiration

Authorized State Agent: James E. Markham Date: 11-19-09 SEE ATTACHED SITE SKETCH  
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Robert + Mary FauceHe Jr PROPERTY LOCATION: SR 1403 Cokesburg RD  
 SUBDIVISION: COVENESS LOT # A  
 Facility Type: SFD ☒ New ☐ Expansion ☐ Repair  
 Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No  
 Type of Wastewater System\*\* 25% REDUCTION System (Initial) Wastewater Flow: 360 GPD  
 (See note below, if applicable ☐  
MANAGER TO 25% REDUCTION (Repair)  
 Installation Requirements/Conditions  
 Septic Tank Size 1000 gallons Number of trenches 3  
 Pump Tank Size \_\_\_\_\_ gallons Exact length of each trench 80 feet  
 Trenches shall be installed on contour at a Trench Spacing: 9 Feet on Center  
 Maximum Trench Depth of: 30-38 inches Soil Cover: 6 inches  
 (Trench bottoms shall be level to  $\pm 1/4"$  (Maximum soil cover shall not exceed  
 in all directions) 36" above the trench bottom)  
 Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM Aggregate Depth: 6 inches below pipe  
 Conditions: \_\_\_\_\_ 2 inches above pipe  
12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markham Date: 11-19-09  
 Construction Authorization Expiration Date: 11-19-14

HTE# 09-5-23222

Permit # 25704

# Harnett County Department of Public Health Site Sketch

PROPERTY LOCATION: SR 1403 Cokesbury RD  
ISSUED TO: Robert + Mary Fawcette JR SUBDIVISION Coverness LOT # A  
Authorized State Agent: Jones E. Markham JR Date: 11-19-09

