

HTE# 09-5-23355

Harnett County Department of Public Health

25857

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: TIMELESS RESIDENTIAL CONST. PROPERTY LOCATION: NC2105
 SUBDIVISION: BEN WOODS LOT # 1
 NEW REPAIR EXPANSION
 Type of Structure: SFD (55'x55')
 Proposed Wastewater System Type: PUMP TO 25% RED. SYS.
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet
 Permit conditions: _____ Permit valid for: Five years
 No expiration

Authorized State Agent: [Signature] REMS Date: 1/13/10 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: TIMELESS RESIDENTIAL CONST. PROPERTY LOCATION: NC2105
 SUBDIVISION: BEN WOODS LOT # 1
 Facility Type: SFD (55'x55') New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** PUMP TO 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable)
PUMP TO 25% REDUCTION SYSTEM (Repair)

Installation Requirements/Conditions

Septic Tank Size <u>1000</u> gallons	Number of trenches <u>3</u>	
Pump Tank Size <u>1000</u> gallons	Exact length of each trench <u>75</u> feet	Trench Spacing: <u>9</u> Feet on Center
	Trenches shall be installed on contour at a	Soil Cover: <u>6</u> inches
	Maximum Trench Depth of: <u>18</u> inches	(Maximum soil cover shall not exceed
	(Trench bottoms shall be level to +/-1/4"	36" above the trench bottom)
	in all directions)	
Pump Requirements: _____ ft. TDH vs. _____ GPM		_____ inches below pipe
Conditions: <u>WATER LINE MUST BE 10' FROM SEPTIC SYSTEM</u>		Aggregate Depth: _____ inches above pipe
		_____ inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] REMS Date: 1/13/10
 Construction Authorization Expiration Date: 1/13/15

HTE# 09-5-23355

Permit # 25857

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: NC2105
ISSUED TO: TIMELESS RESIDENTIAL CONST. SUBDIVISION BEN WOODS LOT # 1

Authorized State Agent: REMS (OLIVER TOLKSDORF) Date: 1/13/10

