25900

HTE# 10-5-23768

Harnett County Department of Public nealth

Improvement Permit

PROPERTY LOCATION: According to the installation of the installati			
ISSUED TO: WYNN CONSTRUCTION SUBDIVISION PIONEER FARMS LOT # 24			
NEW REPAIR EXPANSION Site Improvements required prior to Construction Authorization Issuance:			
Proposed Wastewater System Type: Conventioned			
Projected Daily Flow: 360 GPD			
Number of bedrooms: 3 Number of Occupants: 6 max			
Basement			
Pump Required: □Yes □ No ☑ May be required based on final location and elevations of facilities			
Type of Water Supply: Community Public Well Distance from well Five years			
Permit conditions:			
Authorized State Agent:: Date: 2726 10 SEE ATTACHED SITE SKETCH			
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This			
site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of			
the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.			
Construction Authorization			
(Required for Building Permit)			
The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance			
with the attached system layout.			
ISSUED TO: WYMM CONSTRUCTION PROPERTY LOCATION: POCOCK RD			
SUBDIVISION PIONEER FARMS LOT # 24			
Facility Type: SFD (50'x50') New Expansion Repair			
Basement? ☐ Yes ⋈ No Basement Fixtures? ☐ Yes ⋈ No			
Type of Wastewater System** Conventional (Initial) Wastewater Flow: 360 GPD			
(See note below, if applicable □)			
CONVENTIONAL (Repair)			
Installation Requirements/Conditions Number of trenches 3			
Septic Tank Size 1000 gallons Exact length of each trench 115 feet Trench Spacing: 9 Feet on Center			
Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: inches			
Maximum Trench Depth of: 24 inches (Maximum soil cover shall not exceed			
(Trench bottoms shall be level to $\pm 1/4$ " 36" above the trench bottom)			
in all directions)			
Pump Requirements:ft. TDH vs GPM inches below pipe			
Aggregate Depth: 2 inches above pipe			
Conditions: WATER LINE MYST BE 10 FROM SEPTIC SYSTEM. 12 inches total			
Conditions: WATER LINE MYST BE 10 FROM SERTIC SYSTEM. Aggregate Depth: 2 inches above pipe inches total			
**If			
**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.			
Owner/Legal Representative Signature: Date:			
This Construction Authorization is subject to respectation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This			
Construction Authorization is subject to compliance with the pravisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.			
Authorized State Agent: Date: 226 10			
Construction Authorization Expiration Date: 22615			

Harnett County Department of Public Health Site Sketch

	PROPERTY LOCATON: ROCOCK RO	
ISSUED TO: WYNN CONSTRU	JION SUBDIVISION PIONEER FARMS	LOT # <u>'み</u> ン
Authorized State Agent:	REAS OLIVER TOLKSDOIF Date: 22616	
-	100'	
261	CONVENTIONAL SO X X SOOR	

LETCHER LN