

HTE# 10-5-23794

Harnett County Department of Public Health

25727

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: A+D Properties

PROPERTY LOCATION: SR 1412 Christian Light RD

NEW REPAIR EXPANSION

SUBDIVISION: Forest Trails LOT # 102

Type of Structure: SFD

Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: 25% REDUCTION System

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet

Permit valid for: Five years No expiration

Permit conditions: Water Line + Pavers to be installed AS SHOWN ON layout

Authorized State Agent: James J. Markert for GAS Date: 3-5-10

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: A+D Properties

PROPERTY LOCATION: SR 1412 Christian Light RD

SUBDIVISION: Forest Trails LOT # 102

Facility Type: SFD New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% REDUCTION System (Initial) Wastewater Flow: _____ GPD

(See note below, if applicable MAINTENANCE 25% REDUCTION System (Repair))

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Number of trenches 4

Pump Tank Size _____ gallons

Exact length of each trench 75 feet

Trench Spacing: 9 Feet on Center

Trenches shall be installed on contour at a

Soil Cover: 6 inches

Maximum Trench Depth of: 24" max inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

(Trench bottoms shall be level to +/- 1/4"

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

Conditions: Water Line + Pavers to be installed AS SHOWN ON layout

2 inches above pipe

12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James J. Markert for GAS

Date: 3-5-10

Construction Authorization Expiration Date: 3-5-15

HTE# 10-5-23794

Permit # 25727

Harnett County Department of Public Health Site Sketch

ISSUED TO: At D Properties

PROPERTY LOCATION: SR1412 Christian Light RD

SUBDIVISION Forest Trails

LOT # 102

Authorized State Agent: James E. Marshall EUBS

Date: 3-5-10

