

HTE# 10-5-23999

Harnett County Department of Public Health

25941

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: KENNETH CUMMINGS PROPERTY LOCATION: ALPINE DR
 SUBDIVISION SUMMIT LOT # 83
 NEW REPAIR EXPANSION
 Type of Structure: SFO (48x46')
 Proposed Wastewater System Type: CONVENTIONAL
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet
 Permit conditions: _____ Permit valid for: Five years
 No expiration

Authorized State Agent: [Signature] RENS Date: 3/29/10 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: KENNETH CUMMINGS PROPERTY LOCATION: ALPINE DR
 SUBDIVISION SUMMIT LOT # 83
 Facility Type: SFO (48x46') New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable CONVENTIONAL (Repair))

Installation Requirements/Conditions

Number of trenches 3
 Septic Tank Size 1000 gallons Exact length of each trench 50 feet Trench Spacing: 9 Feet on Center
 Pump Tank Size _____ gallons Trenches shall be installed on contour at a Soil Cover: 12-24 inches
 Maximum Trench Depth of: 24-36 inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
 Conditions: WATER LINE MUST BE 10' FROM SEPTIC SYSTEM. NO
UTILITIES MAY ENCRACH ON INITIAL OR REPAIR AREAS.
12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This

Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] RENS Date: 3/29/10
 Construction Authorization Expiration Date: 3/29/15

HTE# 10-5-23999

Permit # 25941

Harnett County Department of Public Health Site Sketch

ISSUED TO: KENNETH CUMMINGS PROPERTY LOCATION: ALPINE DR
SUBDIVISION SUMMIT LOT # 83

Authorized State Agent: ~~REAS (OLIVER TOLKSDORF)~~ Date: 3/29/10

