

HTE# 10-5-24457

# Harnett County Department of Public Health

26116

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: MARKS RD

ISSUED TO: SIGNATURE HOME BUILDERS INC SUBDIVISION COOPER FARMS LOT # 27

NEW  REPAIR  EXPANSION

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD (65'x36')

Proposed Wastewater System Type: CONVENTIONAL

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement  Yes  No

Pump Required:  Yes  No  May be required based on final location and elevations of facilities

Type of Water Supply:  Community  Public  Well Distance from well 100 feet

Permit valid for:  Five years  
 No expiration

Permit conditions:

Authorized State Agent: [Signature] REWS Date: 6/8/10 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

## Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: SIGNATURE HOME BUILDERS INC PROPERTY LOCATION: MARKS RD  
SUBDIVISION COOPER FARMS LOT # 27

Facility Type: SFD (65'x36')  New  Expansion  Repair

Basement?  Yes  No Basement Fixtures?  Yes  No

Type of Wastewater System\*\* CONVENTIONAL (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable ) CONVENTIONAL (Repair)

|   |   |   |
|---|---|---|
| <b>Installation Requirements/Conditions</b> | Number of trenches <u>2</u>                 | Trench Spacing: <u>9</u> Feet on Center |
| Septic Tank Size <u>1000</u> gallons        | Exact length of each trench <u>75</u> feet  | Soil Cover: <u>24</u> inches            |
| Pump Tank Size _____ gallons                | Trenches shall be installed on contour at a | (Maximum soil cover shall not exceed    |
|   | Maximum Trench Depth of: <u>36</u> inches   | 36" above the trench bottom)            |
|   | (Trench bottoms shall be level to +/- 1/4"  |   |
|   | in all directions)                          |   |

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

Aggregate Depth: 6 inches below pipe  
2 inches above pipe  
12 inches total

Conditions: WATER LINE MUST BE 10' FROM SEPTIC SYSTEM NO UTILITIES MAY ENCRUGH ON INITIAL OR REPAIR AREAS.

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.  
Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] REWS Date: 6/8/10  
Construction Authorization Expiration Date: 6/8/15

HTE# 10-524457

Permit # 26176

# Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: MARKS RD

ISSUED TO: SIGNATURE HOME BUILDERS SUBDIVISION COOPER FARMS LOT # 27

Authorized State Agent: ~~RENS (OLIVER TOLKSDORF)~~ Date: 6/8/10

