

HTE# 10-5-24502

Harnett County Department of Public Health

26153

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Stencil Builders PROPERTY LOCATION: SR 1141 Micro Tower Rd.
 NEW REPAIR EXPANSION SUBDIVISION: Pattar Point II LOT # 164
 Type of Structure: SFD 40'x60' Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: 25% reduction system
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet
 Permit conditions: _____ Permit valid for: Five years No expiration

Authorized State Agent: Bryan McLean, REHS Date: 6/9/2010 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Stencil Builders PROPERTY LOCATION: Micro Tower
 Facility Type: SFD SUBDIVISION: Pattar Point II LOT # 164
 Basement? Yes No New Expansion Repair
 Basement Fixtures? Yes No
 Type of Wastewater System** 25% reduction system (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable)
25% reduction system (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons
 Pump Tank Size _____ gallons
 Number of trenches 1
 Exact length of each trench 150 feet
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 30 inches
 (Trench bottoms shall be level to $\pm 1/4"$ in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM
 Trench Spacing: 9 Feet on Center
 Soil Cover: 18 inches
 (Maximum soil cover shall not exceed 36" above the trench bottom)

Conditions: No utilities allowed in system for repair areas. Aggregate Depth: _____ inches below pipe
All water lines must be at least 10ft. from any part of septic system _____ inches above pipe
 _____ inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McLean, REHS Date: 6/9/2010
 Construction Authorization Expiration Date: 6/9/2015

HTE# 10-5-24502

Permit # 26153

Harnett County Department of Public Health Site Sketch

ISSUED TO: Stancil Builders PROPERTY LOCATOR: Micro Tower Rd.
SUBDIVISION: Patterson Point LOT # 164

Authorized State Agent: Bryan McLean, REHS Date: 6/9/2010

