

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: WYNN CONSTRUCTION
PROPERTY LOCATION: 27 WEST
SUBDIVISION: TINGEN POINTE
LOT # 98
Type of Structure: SFD (60x60)
Proposed Wastewater System Type: PUMP TO 25% REDUCTION
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement: No
Pump Required: Yes
Type of Water Supply: Public
Permit valid for: Five years

Authorized State Agent: [Signature] RENS Date: 6/30/10 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: WYNN CONSTRUCTION
PROPERTY LOCATION: 27 WEST
SUBDIVISION: TINGEN POINTE
LOT # 99
Facility Type: SFD (60x60)
Basement? No
Type of Wastewater System: PUMP TO 25% REDUCTION SYSTEM
(Initial) Wastewater Flow: 360 GPD
Pump To 25% REDUCTION (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size 1000 gallons
Number of trenches 1
Exact length of each trench 260 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Maximum Trench Depth of: 12 inches
(Trench bottoms shall be level to +/- 1/4" 36" above the trench bottom)
in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
Aggregate Depth: _____ inches above pipe

Conditions: DO NOT REMOVE ANY SOIL DURING CLEARING - HAND CLEARING RECOMMENDED. SOIL DEPTH TO BE VERIFIED BY APPLICANT'S SOIL SCIENTIST OR HCHO PRIOR TO INSTALLATION. MINIMUM OF 6" OF COVER NEEDED OVER DRAINFIELD. MAINTAIN ALL SETBACKS.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] RENS Date: 6/30/10
Construction Authorization Expiration Date: 6/30/15

HTE# 10-5-24596

Permit # 26143

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATION: 27 WEST

ISSUED TO: Wynn Construction

SUBDIVISION TIRGEN POINTE

LOT # 98

Authorized State Agent:

RENS (OLIVER TOLKSDORF)

Date: 6/30/10

* WATER LINE MUST BE 10' FROM SEPTIC SYSTEM & REPAIR AREA.

