

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Blackwell Homes
PROPERTY LOCATION: Micro Tower
SUBDIVISION: The Summit
LOT # 112
Type of Structure: SFD 60x50
Proposed Wastewater System Type: conventional
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement: No
Pump Required: May be required based on final location and elevations of facilities
Type of Water Supply: Public
Permit valid for: Five years

Authorized State Agent: Ryan McSwain, R.E.H.S. Date: 7/9/2010 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Blackwell Homes
PROPERTY LOCATION: Micro Tower Rd.
SUBDIVISION: The Summit
LOT # 112
Facility Type: SFD New
Basement? No Basement Fixtures? No
Type of Wastewater System: Conventional (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable) 25% Reduction System (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size
Number of trenches 1
Exact length of each trench 150 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 12 inches
Maximum Trench Depth of: 24 inches
(Trench bottoms shall be level to +/- 1/4" in all directions)
Pump Requirements: ft. TDH vs. GPM
Aggregate Depth: 6 inches below pipe, 2 inches above pipe, 12 inches total

Conditions: Run drain lines on contour. No utilities allowed in the system for repair areas. All water lines must be at least 10 ft. from any part of the septic system

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Ryan McSwain, R.E.H.S. Date: 7/9/2010
Construction Authorization Expiration Date: 7/9/2015

HTE# 10-5-24726

Permit # 26169

Harnett County Department of Public Health Site Sketch

ISSUED TO: Blackwell Homes PROPERTY LOCATOR: Micro Tower Rd.
SUBDIVISION The Summit LOT # 112

Authorized State Agent: George McSwain, L.E.H.S. Date: 7/9/2010

