HTE# 10-5-24814

Harnett County Department of Public Health

Improvement Permit

27307

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: Tingen Rd.
_____SUBDIVISION _ Pattens Point ISSUED TO: Stancil Builders REPAIR □ , NEW 🗹 Site Improvements required prior to Construction Authorization Issuance: Type of Structure: ____SFD 50X25 Proposed Wastewater System Type: 257. Leduction System Projected Daily Flow: 360 Number of bedrooms: _______ Number of Occupants: _______ Basement □Yes ☑ No ☐ May be required based on final location and elevations of facilities Pump Required: □Yes Type of Water Supply:

Community Public

Well Distance from well feet Five years Permit valid for: Permit conditions: ☐ No expiration Date: 2/28/2013 Authorized State Agent: Dun Mc Swain, REHS The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. **Construction Authorization** (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. PROPERTY LOCATION: Tingen Rd.
SUBDIVISION Patters Point ISSUED TO: 5+ ancil Buildear ☐ Expansion ☐ Repair Basement? Yes No Basement Fixtures? ☐ Yes ☐ No Type of Wastewater System** 2572 Red oction System (Initial) Wastewater Flow: 260 GPD (See note below, if applicable □) Number of trenches Installation Requirements/Conditions Exact length of each trench 50 feet Trench Spacing: 9 Feet on Center Septic Tank Size /000 gallons Soil Cover: 6 - 18 inches Pump Tank Size _____ gallons Trenches shall be installed on contour at a Maximum Trench Depth of: 16.36 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: ______ft. TDH vs. _____ GPM _____ inches below pipe Aggregate Depth: inches above pipe Conditions: inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. **If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent: /

Construction Authorization Expiration Date: 2/28/2018

HTE# 10-5-24	814	
--------------	-----	--

Permit # 27307

Harnett County Department of Public Health Site Sketch

_	PROPERTY LOCATON: Tingen Rd.		
ISSUED TO: Stancil Builders	SUBDIVISION Pattons Aint	LOT #	151
<i>^</i>	1 ,		
Authorized State Agent: Luca Milionia	REILS Date: 2/28/2013	7	

