

HTE# 10-5-256262

Harnett County Department of Public Health

26099

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: MARK VAN DE HEY PROPERTY LOCATION: SR1426 Cotton RD
 NEW REPAIR EXPANSION SUBDIVISION _____ LOT # _____
 Type of Structure: SFD Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: MANHOLE TO 25%
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: STUB PLUMBING OUT AT GRADE 15' off of No expiration
BASEMENT - THIS WELL ALLOW TO USE 1000 GPM tank only

Authorized State Agent: James E. Markham Date: 12-14-10 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: MARK VAN DE HEY PROPERTY LOCATION: SR1426 Cotton RD
 SUBDIVISION _____ LOT # _____
 Facility Type: SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** Manhole to 25% collection system (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable)
Manhole to ultra shallow conventional (Repair)

Installation Requirements/Conditions
 Septic Tank Size 1000 gallons Number of trenches 3
 Pump Tank Size 1000 gallons Exact length of each trench 100 feet Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 28" inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to +1/4" 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM _____ inches below pipe
 Aggregate Depth: 2 inches above pipe
 Conditions: MANHOLE WILL NOT BE NEEDED IF PLUMBING _____ inches total
is stubbed out at natural grade 15' off of basement.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Markham Date: 12-14-10
 Construction Authorization Expiration Date: 12-14-15

HTE# 10-5-25626R

Permit # 26099

Harnett County Department of Public Health Site Sketch

ISSUED TO: MARK VAN DE HEG PROPERTY LOCATOR: SA 1426 Cotton RD
SUBDIVISION _____ LOT # _____

Authorized State Agent: Jones Markant @ RAS Date: 12-14-10

* IF Plumbing IS STUBBED OUT AT grade 15' off of Basement pump well NOT BE NEEDED. DEEP PLUMBING CAUSES Septic System to RUN INTO WOODED AREA, WHICH WILL THEN HAVE TO BE CLEARED.

