HTE# 10-5- 25 704 Harnett county Department of Public Heartn

Improvement Permit

26311

A building permit cannot be issued with only an Improvement Permit Rengency Honer SUBDIVISION Ashe Food Site Improvements required prior to Construction Authorization Issuance: Type of Structure: SFO Proposed Wastewater System Type: 25% Reduction System Projected Daily Flow: _ 360 Number of bedrooms: Number of Occupants: 6 Basement Yes Pump Required: □Yes May be required based on final location and elevations of facilities I No Type of Water Supply:

Community Public Well Distance from well ______ feet Five years Permit valid for: Permit conditions: ■ No expiration Authorized State Agent: Date: 12 13 2 40 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Regency Homes PROPERTY LOCATION: Marks Rd.

SUBDIVISION Ashe ford LOT # 126 Basement? Yes Basement Fixtures?

Yes 25 % Reduction System (Initial) Wastewater Flow: 360 GPD Type of Wastewater System** (See note below, if applicable) 25% Reduction Tysten (Repair) Number of trenches 2 Exact length of each trench 90 feet Trench Spacing: 9 Feet on Center Septic Tank Size /OOO gallons Pump Tank Size gallons Trenches shall be installed on contour at a Soil Cover: 6-12 Maximum Trench Depth of: 18-24 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: _____ft. TDH vs. ____ GPM _ inches below pipe Conditions: Drainlines to be run on contour. System layout

Aggregate Depth:

inches above pipe

inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. **If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent; Construction Authorization Expiration Date: (2/13/2015

Harnett County Department of Public Health Site Sketch

| 0 1 | PROPERTY LOCATON: Marke Rd. | | |
|------------------------------------------|-----------------------------|-------|-----|
| ISSUED TO: Regency Homes | subdivision Acheford | LOT # | 126 |
| | 0 - 40 | | |
| Authorized State Agent: / Sugar Police / | REHS Date: 12/13/240 | | |

